

Record #	Record Type	Applicant Name	Date Submitted	Address	Record Status
COMB-22-50	Commercial Building Permit	John DellaMea	7/25/2022 21:48	555 SANFORD AV, MOCKSVILLE, NC 27028	Active
COMB-22-48	Commercial Building Permit	CHRIS JOHNSON	7/23/2022 14:45	181 PARKER RD, MOCKSVILLE, NC 27028	Active
COMB-22-49	Commercial Building Permit	Hannah Shockey	7/25/2022 12:50	7700 NC HWY 801 S, COOLEEMEE, NC 27014	Active
COMB-22-47	Commercial Building Permit	David Beals	7/21/2022 18:09	552 CORNATZER RD, MOCKSVILLE, NC 27028	Active
COMB-22-45	Commercial Building Permit	Tony Stewart	7/14/2022 14:48	221 GRAY SHEEKS RD, ADVANCE, NC 27006	Active
COMB-22-46	Commercial Building Permit	Craig Hendrix	7/14/2022 15:16	5431 US HWY 158, BERMUDA RUN, NC 27006	Active

Contractor Company Name	Jurisdiction	Brief Project Description	Type of Structure	Total Square Feet	Construction Cost
		Selective demolition and renovation of existing building classified as business, factory (F-1), and storage (S-2). The renovation includes new interior walls and finishes for new entrance vestibule, breakroom, restrooms, training rooms, offices, storage areas, testing areas, and research and development. Walls to be constructed out of CMU, metal studs with gypsum board, and a combination of CMU with gypsum board furring walls. Finishes include painting of existing structure, installing new ACT ceilings, new resilient and tile flooring, new doors & frames, new storefront entrance with new entrance canopy, new concrete ADA walkway with steps and handrailing, and refurbish existing metal building with new metal panels. Electrical modifications includes reworking existing panels, adding a new panel and transformer, adding new circuits and light fixtures, and modifying the existing fire alarm system to work with the new layout. Modify the existing fire suppression system to work with new room layout and ceiling systems. HVAC modifications include adding one (1) new rooftop unit, six (6) new slit systems, and two (2) new exhaust fans, reworked and new compressed air system, including associated duct work, air piping, tanks, valves, grilles, dampers, louvers, gas piping to the new RTU, and associated controls. Plumbing modifications include new water closets, urinals, lavatories, drinking fountains, water heater, and floor drains for the womans & mens restroom, breakroom, and janitor's closet.Â	Remodel	14785	1204739
Choate Construction Company CKJ BUILDING & DESIGN, LLC	Mocksville Davie County	RENOVATE THE MENS RESTROOM	Remodel	132	37900
Guy Roofing	Davie County	Remove the existing membrane exposing the plywood decking. Mechanically Attach a 60 Mil TPO roof system.	Shell Building	3000	25900
Nations Roof of Carolina	Davie County	Reroof project. Remove existing edge metals & memebrane leaving the existing insulation in place; replace any wet insulation like for like. install new 1/4" coverboard and new PVC membrane. Install new edge metals, install membrane and metal to manufactures details for a 20 yr warranty. collocation on existing tower, add pad with equipment, add	Remodel	23530	342000
Horne Brothers Communications Craig Hendrix Construction Co. Inc.	Davie County Bermuda Run	generator with pad,add electircal Building a greenhouse.	Accessory Structure Accessory Structure	350 2400	24860 295000
				<b>TOTAL</b>	<b>1930399</b>